

DEVELOPMENT TEST REPORT

Report No. ARAI/AED/20212022/3100010138/DT/0370

CONFIDENTIAL

Dated: 24-JUN-2021

1.0	Name and address of the customer	ROTEX MANUFACTURERS & ENGINEERS PRIVATE LIMITED R852/853, TTC Industrial Area, Rabale MIDC, Navi Mumbai, Maharashtra, India. 400701	
2.0	Customer letter reference	Email Dated: 10-MAY-2021	
3.0	Description of the Device Under Test (DUT)	DUT Name	Electrohydraulic Actuator
		Manufacture Name	ROTEX MANUFACTURERS & ENGINEERS PRIVATE LIMITED
		Model Name	EHF SERIES
		Model No	EHF-RO-DRS-A-HY-50-X-E7-D-SP-EFC-E-20-H-4MO-M-1A2-P-M-C2
		Part No.	1000816/051/02/01
		Hardware Version	EHA-V2
		Software Version	1.6.2
4.0	Test objective	To carry out EMI/EMC tests as per details given in table 9.0	
5.0	Condition of the test component	The test component was received in good condition.	
			

		 Digitally signed by MANOJ MADHUKAR DESAI Date: 2021.07.01 08:14:15 +05'30'
A S MADALGI MANAGER	A A PAPADE MANAGER	M M DESAI GENERAL MANAGER

Page 1 of 4

6.0 FUNCTIONALITY VERIFICATION

DUT was a Electrohydraulic Actuator powered with 440V AC supply. 230V AC supply was given for emergency shutdown of device. Electrohydraulic Actuators are self-contained actuators operated solely by electrical power, used to operate the Valves for ON/OFF (Emergency Shut Down Valves) and Modulating Application. For functionality verification pressure and position was monitored during test and Valve status with percentage was displayed On Unit was also monitored.

8.0 FUNCTIONAL PERFORMANCE CRITERIA

8.1 Criteria A

Normal performance within limits specified by the manufacturer, requestor or purchaser.

8.2 Criteria B

Temporary loss of function or degradation of performance which ceases after the disturbance ceases, and from which the equipment under test recovers its normal performance, without operator intervention.

8.3 Criteria C

Temporary loss of function or degradation of performance, the correction of which requires operator intervention.

8.4 Criteria D

Loss of function or degradation of performance which is not recoverable, owing to damage to hardware or software, or loss of data.

9.0 TEST DETAILS

Sr. No.	Test Title	Annexure No.	Number of Pages	Reference Standard	Customer Acceptance Criteria	Functional Performance Criteria
9.1	Radiated RF Immunity – Enclosure Port	01	06	IEC 61000-4-3:2006	Criteria A	Criteria A

A S MADALGI MANAGER	A A PAPADE MANAGER

10.0 LIST OF TEST EQUIPMENT'S			
Radiated Immunity Equipment List			
Description	ARAI ID	Status	Cal Due Date
Signal Generators			
Rohde & Schwarz SML 02 Signal Generator	AED/GEN/02	■	19/11/2022
Rohde & Schwarz SMB 100A Signal Generator	AED/GEN/04	□	27/12/2022
Antennas			
Frankonia Gmbh BTA-M Broad Band Antenna (1MHz-3000MHz)	AED/ANT/09	■	N/A
ETS-Lindgren 3109PX Biconical Antenna (Type 2) (20MHz-300MHz)	AED/ANT/11	■	N/A
Schwarzbeck Mess Elektronik BBHA 9120 D Double Ridge Horn Antenna (1GHz-18GHz)	AED/ANT/14	□	N/A
Amplifiers			
AR 500W1000AM1 500W RF Power Amplifier	AED/RFAMP/04	■	N/A
AR BLMA 0820-200 200W RF Power Amplifier	AED/RFAMP/05	■	N/A
AR 1000A225 RF Power Amplifier	AED/RFAMP/06	□	N/A
Power Sensors			
Rohde & Schwarz NRP-Z91Power Sensor	AED/Power Sensor/04	■	N/A
Rohde & Schwarz NRP-Z91Power Sensor	AED/Power Sensor/05	■	N/A
Power Meters			
Rohde & Schwarz NRP2 Power Meter	AED/RFPM/03	■	N/A
Laser Powered Field Probe			
RF FL 7006 Star Probe 2 Laser Powered Field Probe	AED/Field Probe/07	□	18/04/2022
Oscilloscopes			
Tektronics DPO 7104 Digital Phosphor Oscilloscope	AED/OSC/05	□	---
Tektronics DPO 3052 Digital Phosphor Oscilloscope	AED/OSC/07	□	30/08/2022
Rohde & Schwarz RTM 2052 Digital Oscilloscope	AED/OSC/09	□	30/08/2022
Test Facility			
Frankonia Gmbh Semi-Anachoic ALSE Chamber, ARAI Pune.	AED/ALSE/02	■	29/09/2022
Software			
Rhode & Schwarz EMC32 Measurement Software Ver. 9.21.00	N/A	■	N/A
Miscellaneous			
Aplab L3210 Regulated DC Power Supply	AED/RPS/18	■	N/A
Freemans Measuring Tape	AED/TAPE/01	□	23/12/2022
Automotive Battery 12V	N/A	□	N/A

Report No. ARAI/AED/20212022/3100010138/DT/0370
Dated: 24-JUN-2021

CONFIDENTIAL

This test report pertains only to the components / parts / assemblies / vehicles etc., actually tested at ARAI in the presented condition based on the documents / information produced / submitted by the customer. The issuance of this test report alone does not indicate any measure of approval, certification, supervision, control of quality surveillance by ARAI of the product. No extract, abridgement or abstraction from this test report shall be published or used to advertise the product without the written consent of the Director, ARAI, who reserves the absolute right to agree or reject all or any of the details of any items of publicity for which consent may be sought. ARAI is in no way responsible for any misuse of copying of any design / type / system in connection with entire vehicle/components/parts and assemblies. Breach of any statutory provision of Indian laws or laws of other countries, will be the sole responsibility of the customer and ARAI shall not be liable for any claims or damages, made by the party, whatsoever. The customer shall alone be liable for the same and undertakes to indemnify ARAI in this regard. Further, the ARAI has the right to initiate cancellation / withdrawal of the certificate / report issued, in case of any fraud, misrepresentation, when it surfaces and comes in the knowledge of ARAI. The appropriate local courts at Pune shall have the jurisdiction in respect of any dispute, claim or liability arising out of this report.

Place of Issue: ARAI, Pune.

A S MADALGI MANAGER	A A PAPADE MANAGER

ANNEXURE 01

1.1 TEST SPECIFICATIONS

TEST DETAILS	RADIATED SUCCEPABILITY TEST AS PER IEC 61000-4-3:2006 STANDARD
TEST DATE	07-JUN-2021
TEST LOCATION	EMI/EMC TEST LAB, KOTHRUD, ARAI

1.2 DUT OPERATING CONDITIONS

DUT MODE OF OPERATION	FULL OPERATING ☒	PARTIAL OPERATING ☐	POWER ON STATE ☐
DIAGNOSTIC TOOLS CONNECTED	CAN BUS CONV. ☐	USB BUS CONV. ☐	RS232 BUS CONV. ☐

1.3 MONITORING OF DUT

PASS/FAIL criteria automatically controlled by EMC Software ☐	PASS/FAIL criteria manually controlled by Operator ☒
PASS/FAIL criteria not verified ☐	PASS/FAIL criteria controlled and evaluated by the Customer ☐

1.4 LABORATORY ENVIRONMENT TEST CONDITIONS 4

AMBIENT TEMPERATURE	+ 25.7°C.	Required (23±5)°C.	RELATIVE HUMIDITY	50.5 %RH.	----
---------------------	-----------	--------------------	-------------------	-----------	------

1.5 TEST SETUP DETAILS

DUT Setup Details	Status	Remarks
a) Test setup was done according to	IEC 61000-4-3:2006	---
b) Test table surface	Wooden ☐ Metallic ☒	---
c) Test table 0.80 m above the ALSE chamber ground floor	Yes ☐ No ☒	---
d) Whether DUT and the wiring harness of the DUT was above the ground plane?	Yes ☒ No ☐	---
e) Whether DUT was grounded (GND) or isolated (ISO) from the ground plane?	GND ☐ ISO ☒	---

A S FARNANDES
TEST ENGINEER

DUT Setup Details	Status	Remarks
f) Antenna height from the ALSE chamber ground plane during the test.	1 m	---
g) Antenna distance from the DUT.	2 m	---
h) Antenna phase center focused to DUT	Yes	---
i) No. of DUT orientations	1	---

1.6 DUT SUPPLY VOLTAGE DETAILS		
A.C. Supply voltage	440V A.C. System	Current Consumption
A.C. Mains supply	(440, ± 5) V ☒	<5 A
D.C. Supply voltage	12/24/32V D.C. System	Current Consumption
D.C. Supply (L= Positive Line and PE= Negative Line)	(12, ± 1) V ☐	---
	(24, ± 1) V ☐	---
	(32, ± 1) V ☐	---

1.7 TEST PARAMETERS				
Frequency Range	80 MHz to 1000 MHz ☒		1000 MHz to 2700 MHz ☒	
Frequency Step Size	1% Logarithmic			
Field Strength	1 V/m ☐	3 V/m ☐	10 V/m ☒	30 V/m ☐
Dwell Time	3 Sec. (Required >0.5Sec as per std.)			
Antenna Polarization	Horizontal ☒		Vertical ☒	
Test Signal Quality	Any spurious spectral line shall be at least 15 dB below the carrier level.			
Frequency Range with Modulation	80 MHz to 1000 MHz ☒		1000 MHz to 2700 MHz ☒	
Frequency Modulation Details	Amplitude Modulation (AM) (80% in depth with 1 kHz sine wave) ☒	AM(Peak)=CW(Peak) ☐		
		AM(Peak)>CW(Peak) ☒		
		AM(RMS)=CW(RMS) ☐		
	Continuous Wave (CW) ☐	Unmodulated Sine Wave ☐		

A S FARNANDES TEST ENGINEER	

1.8 TEST PROCEDURE

1.8.1 The radiated immunity tests were done inside the anechoic chamber.

1.8.2 **CALIBRATION:** The calibration was done with a closed loop system where the field strength levels were measured using a field probes that was placed in close proximity to the DUT. The calibration file contains the signal generator levels and power levels required to generate a specific field strength level over the test frequency range.

1.8.3 **VERIFICATION:** The calibrated settings were verified by emitting a field and monitoring field strength.


1.8.4 **DUT IMMUNITY:** The DUT was tested by replaying the calibrated test levels (the signal generated levels) from the calibration file. The DUT was tested for immunity over a fixed time called "dwell period" at a particular frequency with the desired field strength.

1.9 TEST OBSERVATION:

Sr. No.	Frequency Range	Modulation	Antenna Polarization	Observation
1.0	80 MHz to 1000 MHz	Amplitude Modulation (AM)	Vertical/ Horizontal	No deviation was Observed. Performance criteria A
2.0	1000 MHz to 2700 MHz	Amplitude Modulation (AM)	Vertical/ Horizontal	No deviation was Observed. Performance criteria A

A S FARNANDES
TEST ENGINEER


1.10 TEST SETUP PHOTO




**A S FARNANDES
TEST ENGINEER**

1.11 MEASUREMENT GRAPH

1.11.1 Frequency Range from 80 MHz to 1000 MHz with Amplitude Modulation (AM) with Horizontal Polarization




1.11.2 Frequency Range from 80 MHz to 1000 MHz with Amplitude Modulation (AM) with Vertical Polarization




**A S FARNANDES
TEST ENGINEER**

1.11.3 Frequency Range from 1000 MHz to 2700 MHz with Amplitude Modulation (AM) with Horizontal Polarization



1.11.4 Frequency Range from 1000 MHz to 2700 MHz with Amplitude Modulation (AM) with Vertical Polarization



A S FARNANDES ENGINEER	A A PAPADE MANAGER

END OF ANNEXURE 01